

**TOWN OF BLIND RIVER
REQUEST FOR TENDER
NEW BLIND RIVER WATER TREATMENT PLANT INTAKE AND LOW LIFT PUMPING STATION
CONTRACT NO. PS-2026-01**

**ADDENDUM #11
March 17th, 2026**

This addendum shall form part of the Contract Documents. The Addendum issued shall be indicated in FT.05 ADDENDA of the FORM OF TENDER.

CLARIFICATION

The estimated earth and rock quantities for site grading and LLPS excavation are as follows:

Site Grading, Access & Servicing

Title	Unit Rate
Earth Excavation	250m ³
Rock Excavation	0m
Rock Trenching – Intake Line	52m
Rock Trenching – Services	14m

LLPS Building Footprint

Title	Unit Rate
Earth Excavation	3,700m ³
Rock Excavation	480m ³

The Building Footprint excavation quantities are based on a 0.5m offset from the building footings, excavated at 2:1 sideslopes in earth.

The Owner will complete a topographic survey of the grubbed site and stripped rock surface, once completed by the contractor. These surveys will be utilized by the Contract Administrator to calculate the actual earth excavation and rock excavation completed to design elevations as a neat volume. No allowance for over blasting will be measured.

QUESTIONS & ANSWERS

Q1: Current proposed 400mmØ HDPE Raw Intake includes an externally mounted 125mmØ Carrier conduit to run parallel. Would the Owner consider installation of the carrier conduit inside the 400mmØ Raw intake? This has been accepted in other similar Raw Water Intake installations.

A1: No. A minimum 400mmØ ID is required. See Addendum 9.

Q2: Considering the changes in Addendum 8, will the Owner be issuing a revised Form of Tender?

A2: No.

Q3: We note HDD scope has been deleted from the Tender in lieu of Open cut. Will the Owner accept a portion of the proposed work be completed via HDD?

A3: See Addendum 10.

- Q4: A number of form of tender changes have been made, are we expected to cut and paste the changes into the form or are you to provide a final updated copy?**
- A4: Bidders shall update the form of tender per the changes issued. The Owner will not be providing a revised Form of Tender.
- Q5: Per the adjustments to the division 2 pricing, we are only submitting the overview divisional breakdown and the detailed breakdown is to be completed after the fact as per the notes, you note costs are to be paid based on the unit rates but wanted to make sure in our divisional breakdown the total cost based on our quantities is to be included and the rates provided after the fact.**
- A5: The unit rates for earth excavation, rock excavation and rock trenching are required to be submitted as part of the bid. The Table provided under Addendum 10 can be inserted after the "Total Price for Division 2". The provided unit rates and estimated excavation quantities are to be used by bidders to calculate their bid values to be presented within the "Total" for the applicable sections within the Division.
- Q6: We respectfully request approval of RuhRPumpen as an alternate manufacturer for the section 11210.**
- A6: No ruling on proposed alternate equipment as acceptable will be made prior to acceptance of a Bidder Submission. For further information Bidders shall refer to Specification Section 01200 – Alternatives.
- Q7: As there have been several changes to the bid form (contract price breakdown) line items, please provide the revised and final bid form so we can proceed with pricing the project.**
- A7: See Answer A4 above.
- Q8: Regarding the Miscellaneous Allowance table, prior to addendum #9, there was a mathematical error in the subtotal field. The total value of the line items would be \$1,050,000.00.**
- A8: Correct. See Addendum #3.
- Q9: The referenced earth and rock excavation quantities have not been provided. Please provide the applicable quantities to enable pricing of Division 2 works.**
- A9: See Clarification Section above.

End of Addendum 11